

Lift Plan Pre-Submission Checklist

The checks a CPCS A61 Appointed Person runs before a lift plan is accepted. Work through it before you submit and you remove most of the reasons plans get rejected.

TECHNICAL ACCURACY

1. Crane / equipment capacity verified against manufacturer data
2. Load weight and centre of gravity correctly assessed
3. Radii and lift heights properly calculated
4. Configuration (boom length, counterweight, hitch) appropriate
5. Ground bearing loads calculated and addressed
6. Percentage utilisation against project threshold

REGULATORY COMPLIANCE

7. LOLER 1998 Regulation 8 met
8. BS 7121 principles applied
9. ISO 10567 used correctly for excavator duties
10. Equipment thorough examination referenced and current
11. Lifting accessories properly specified with WLL evidence
12. Personnel competencies named and verified

RISK ASSESSMENT QUALITY

13. All foreseeable hazards identified
14. Site-specific factors (services, edges, neighbours)
15. Control measures adequate, proportionate and workable
16. Residual risk acceptable
17. Weather limits and stop conditions clear

METHOD STATEMENT WORKABILITY

18. Step-by-step procedure logical and complete
19. Matches the lift plan drawing
20. Roles and responsibilities clear (AP, LS, Crane Sup, Op, Slinger)
21. Communication arrangements specified
22. Emergency and stop-work procedures

Category A — technically correct, compliant and site-suitable; the lift can proceed. **Category B** — must be amended before the lift goes ahead, with every finding referenced to the relevant standard.

This checklist is general guidance for preparing lifting documentation. It does not replace a site-specific lift plan, and it does not discharge the duty under LOLER 1998 Regulation 8 to have every lifting operation planned by a competent person.